

No.	Street	Length	Width	Thickness (inches)	lbs./inch S.Y.	Tons	Cost per Ton	Extension
1	Miller Street Loop 274 to West end	2200.0	20.0	1.5	165.0	405.0	\$68.16	\$27,604.80
2	Peach Street Anderson to East End	800.0	18.0	1.5	165.0	135.0	\$68.16	\$9,201.60
3	Cemetery Road Park to Downing	1550.0	21.0	1.5	165.0	300.0	\$68.16	\$20,448.00
4	Gifford Lane Gifford Rd. to S. Downing	2500.0	18.0	1.5	165.0	415.0	\$68.16	\$28,286.40
5	Columbia Live Oak to Mulberry	950.0	20.0	1.5	165.0	175.0	\$68.16	\$11,928.00
6	Columbia Miller to Live Oak	1600.0	20.0	1.5	165.0	300.0	\$68.16	\$20,448.00
7	Kiber Anderson to Loop 227	1800.0	20.0	1.5	165.0	340.0	\$68.16	\$23,174.40
8	Miller Valderas to Rock Island	1100.0	35.0	1.5	165.0	360.0	\$68.16	\$24,537.60
9	Miller Rock Island to McBride	900.0	35.0	1.5	165.0	290.0	\$68.16	\$19,766.40
10	Miller McBride to Downing	1100.0	35.0	1.5	165.0	360.0	\$68.16	\$24,537.60
11	Piney Way Valderas to S.H. 288 B	1400.0	20.0	1.5	165.0	260.0	\$68.16	\$17,721.60
12	N. Tinsley Wilkins to Nottingham	1100.0	27.0	1.5	165.0	275.0	\$68.16	\$18,744.00
13	N. Tinsley Nottingham to Ridgecrest	950.0	27.0	1.5	165.0	240.0	\$68.16	\$16,358.40
14	Hancock Myrtle to Live Oak	1150.0	20.0	1.5	165.0	210.0	\$68.16	\$14,313.60
15	N. Rock Island Northridge to South	850.0	28.0	1.5	165.0	220.0	\$68.16	\$14,995.20

No.	Street	Length	Width	Thickness (inches)	lbs./inch S.Y.	Tons	Cost per Ton	Extension
16	Locust Loop 274 to T.J. Wright	700.0	20.0	1.5	165.0	130.0	\$68.16	\$8,860.80
17	Kyle Street Valderas to N. Rock Island	1550.0	28.0	1.5	165.0	400.0	\$68.16	\$27,264.00
18	Lorraine Street Valderas to N. Rock Island	1550.0	28.0	1.5	165.0	400.0	\$68.16	\$27,264.00
19	Miller Street Chenango to Arcola	450.0	20.0	1.5	165.0	85.0	\$68.16	\$5,793.60
20	Miller Street Arcola to Valderas	250.0	20.0	1.5	165.0	50.0	\$68.16	\$3,408.00
21	Live Oak Erskine to Parrish	800.0	20.0	1.5	165.0	150.0	\$68.16	\$10,224.00
22	Erskine Myrtle to Live Oak	1100.0	22.0	1.5	165.0	225.0	\$68.16	\$15,336.00
23	Valderas Swift to Wilkins	1750.0	36.0	1.5	165.0	580.0	\$68.16	\$39,532.80
24	Valderas Wilkins to Cedar	1300.0	36.0	1.5	165.0	430.0	\$68.16	\$29,308.80
25	Cedar Street SH 288B to Willow	1300.0	36.0	1.5	165.0	430.0	\$68.16	\$29,308.80
26	Cedar Street Willow to N. Tinsley	1500.0	36.0	1.5	165.0	500.0	\$68.16	\$34,080.00
27	Cedar Street N. Tinsley to SH 35	1500.0	36.0	1.5	165.0	500.0	\$68.16	\$34,080.00
28	Munson Erskine to 288 B	600.0	20.0	1.5	165.0	110.0	\$68.16	\$7,497.60

Total

**\$564,024.00**

**RLH Recommendation**

No.	Street	Length	Width	Thickness (inches)	lbs./inch S.Y.	Tons	Cost per Ton	Extension
4	Gifford Lane Gifford Rd. to S. Downing	2500.0	18.0	1.5	165.0	415.0	\$68.16	\$28,286.40
21	Live Oak Erskine to Parrish	800.0	20.0	1.5	165.0	150.0	\$68.16	\$10,224.00
22	Erskine Myrtle to Live Oak	1100.0	22.0	1.5	165.0	225.0	\$68.16	\$15,336.00
24	Valderas Wilkins to Cedar	1300.0	36.0	1.5	165.0	430.0	\$68.16	\$29,308.80
25	Cedar Street SH 288B to Willow	1300.0	36.0	1.5	165.0	430.0	\$68.16	\$29,308.80
28	Munson Erskine to 288 B	600.0	20.0	1.5	165.0	110.0	\$68.16	\$7,497.60
<b>Total</b>								<b>\$119,961.60</b>

4	We did level up last year and need to finish this year.
21	Construction in area and need to fix roadway
22	Construction in area and need to fix roadway
24	Will do this part this year and hopefully Wilkins to Swift next year
25	Will do this part this year and hopefully from Willow to N. Tinsley or S.H. 35 next year
28	Construction in area and need to fix roadway