



CITY OF FARMINGTON
110 West Columbia
Farmington, Missouri 63640
573.756.1701

BRAY ROAD IMPROVEMENTS

ADDENDUM #1

Date: 3/27/2026

This Addendum forms a part of the Bidding and Contract Documents and modifies the original Bidding Documents.

FAILURE TO ACKNOWLEDGE RECEIPT OF ADDENDUM MAY SUBJECT BIDDER TO DISQUALIFICATION.

Replace the Itemized Bid Form with the Revised Itemized Bid Form attached.

Other Items

This project is tax exempt.

END OF ADDENDUM NO. 1

Project: Bray Road Improvements

Itemized Bid Form

Revised: 3/27/26

BASE BID

Number	Description	Unit	Amount	Unit Price	Extended Cost
1	MOBILIZATION	LS	1		
2	CLEARING AND STRIPPING	LS	1		
3	EARTH EXCAVATION (EXCESS DIRT)	CY	220		
4	TELEPHONE CONDUIT REMOVAL (CONDUIT NOT IN USE PER AT&T)	LF	2,001		
5	TELEPHONE BOX/RISER/PEDESTAL REMOVAL	EA	5		
6	15" CMP PIPE REMOVAL	LF	55		
7	18" CMP PIPE REMOVAL	LF	424		
8	24" CMP PIPE REMOVAL	LF	138		
9	ADJUST MANHOLE TO GRADE	EA	2		
10	AREA INLET TO BE REMOVED AND REPLACED	EA	1		
11	EXISTING SIGN TO BE REMOVED AND RELOCATED	EA	6		
12	REMOVE AND RELOCATE MAILBOX/CARRRER	EA	2		
13	EXISTING OVERHEAD POLE/SERVICE TO BE REMOVED	EA	1		
14	GRAVEL ENTRANCE REMOVAL	SF	1,204		
15	ASPHALT PAVEMENT REMOVAL	SF	50,607		
16	10' DIAMETER MANHOLE	EA	1		
17	10' DIAMETER CURB INLET	EA	3		
18	10' DIAMETER DOUBLE CURB INLET	EA	1		
19	CURB INLET	EA	16		
20	DOUBLE CURB INLET	EA	5		
21	AREA INLET	EA	5		
22	18" CLASS V RCP	LF	39		
23	30" CLASS III RCP	LF	45		
24	36" CLASS V RCP	LF	225		
25	36" RCP FLARED END SECTION	EA	2		
26	108"X36" CLASS III RCP BOX CULVERT	LF	90		
27	STREET LIGHT STANDARD	EA	7		
28	PEDESTRIAN HANDRAIL	LF	100		
29	CAST-IN-PLACE CONCRETE WALL	SF	330		
30	MODOT TYPE 2 DITCH LINER	SF	5,755		
31	CONCRETE SWALE REWORK	SF	80		
32	TRENCH DRAIN	LF	30		
33	CONCRETE CURB AND GUTTER	LF	3,525		
34	ROLLED CURB	LF	18		
35	SEEDING (WITH STRAW BLANKET)	ACRE	1.88		
36	MODIFIED URETHANE PAVEMENT STRIPING - LINE 6"	LF	3,890		
37	MODIFIED URETHANE PAVEMENT STRIPING - TURN ARROW	EA	6		
38	TRAFFIC CONTROL	LS	1		
			BASE BID SUB TOTAL		

Project: Bray Road Improvements

Itemized Bid Form

Number	Description	Unit	Amount	Unit Price	Extended Cost
BID ALTERNATE 1					
43	4" TYPE 5 AGGREGATE BASE	Tons	1,530		
44	8" CONCRETE PAVEMENT	CY	2,266		
				BID ALTERNATE 1 SUB TOTAL	
BID ALTERNATE 2					
45	8" TYPE 5 AGGREGATE BASE	Tons	3,060		
46	8" ASPHALT BASE	Tons	4,440		
47	2" ASPHALT SURFACE	Tons	1,110		
				BID ALTERNATE 2 SUB TOTAL	
BID ALTERNATE 3					
48	18" RCP	LF	930		
49	24" RCP	LF	610		
50	30" RCP	LF	335		
51	36" RCP	LF	815		
				BID ALTERNATE 3 SUB TOTAL	
BID ALTERNATE 4					
52	18" ADS HP PIPE	LF	930		
53	24" ADS HP PIPE	LF	610		
54	30" ADS HP PIPE	LF	335		
55	36" ADS HP PIPE	LF	815		
				BID ALTERNATE 4 SUB TOTAL	
BID ALTERNATE 5					
56	5' WIDE CONCRETE SIDEWALK	SF	15,750		
57	CURB RAMPS WITH DETECTABLE WARNING STRIP	EA	20		
				BID ALTERNATE 5 SUB TOTAL	