

VIRGINIA STREET, YALE AVENUE, WESLEY DRIVE, ALDERGATE STREET, & HAW
STREET WATER MAIN IMPROVEMENT

Bid Form

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization, Demobilization, Startup, Permits, Insurance and Bonds	LS	1		
2	Removal and Disposal of Excavated Materials	CY	2,064		
3	Existing Fire Hydrant Removal (To be Returned to City)	EA	2		
4	Existing Water Meter Removal (Includes Removal of Meter Pit, Meter Setter and Meters. Meters to be returned to City)	EA	84		
5	8-Inch Diameter SDR 21 Class 200 PVC Water, In Open-Cut Trench	LF	4,277		
6	Detail "A"	EA	2		
7	Detail "B"	EA	1		
8	Detail "C"	EA	1		
9	Detail "D"	EA	1		
10	Detail "E"	EA	1		
11	8"x8"x8" Stainless Steel Tapping Sleeve and Tapping Valve	EA	4		
12	8-Inch 45° M.J. Bend	EA	4		
13	8-Inch M.J. Gate Valve	EA	8		
14	6-Inch M.J. Cap	EA	1		
15	4-Inch M.J. Cap	EA	2		
16	3/4-Inch Corporation Stop	EA	1		
17	Fire Hydrant Assembly	EA	7		
18	¾-Inch Diameter Water Service Connection (Includes Meter Pit, Meter Setter, P.E. Tubing, Corp. Stop, Curb Valve Pack Joint, etc.)	EA	84		
19	Compacted Granular Backfill	TON	3,343		
20	Asphalt Pavement Repair (Includes Curb & Gutter Repair)	SY	1,389		
21	Finish Grading and Seeding	AC	0.63		
Total Base Bid					