

Bid Form

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization, Demobilization, Startup, Permits, Insurance and Bonds	LS	1		
2	Removal and Disposal of Excavated Materials	CY	1,559		
3	Existing Fire Hydrant Removal (To be Returned to City)	EA	6		
4	Existing Water Meter Removal (Includes Removal of Meter Pit, Meter Setter and Meters. Meters to be returned to City)	EA	31		
5	8-Inch Diameter SDR 21 Class 200 PVC Water, In Open-Cut Trench	LF	2,797		
6	Detail "A"	EA	1		
7	Detail "B"	EA	1		
8	Detail "C"	EA	1		
9	Detail "D"	EA	1		
10	Detail "E"	EA	1		
11	8"x8"x8" Stainless Steel Tapping Sleeve and Tapping Valve	EA	1		
12	6"x6"x6" Stainless Steel Tapping Sleeve and Tapping Valve with 6"x8" M.J. Increaser	EA	1		
13	8-Inch 45° M.J. Bend	EA	7		
14	8-Inch M.J. Gate Valve	EA	8		
15	6-Inch M.J. Cap	EA	2		
16	4-Inch M.J. Cap	EA	1		
17	Fire Hydrant Assembly	EA	8		
18	2-Inch Diameter Water Service Connection Transfer (Includes P.E. Tubing, Corp. Stop, Curb Valve, Pack Joint, etc.)	EA	1		
19	1-Inch Diameter Water Service Connection Transfer (Includes P.E. Tubing, Corp. Stop, Curb Valve, Pack Joint, etc.)	EA	1		
20	¾-Inch Diameter Water Service Connection Transfer (Includes P.E. Tubing, Corp. Stop, Curb Valve, Pack Joint, etc.)	EA	3		
21	¾-Inch Diameter Water Service Connection (Includes Meter Pit, Meter Setter, P.E. Tubing, Corp. Stop, Curb Valve Pack Joint, etc.)	EA	31		
22	Compacted Granular Backfill	TON	2,525		
23	Concrete Pavement Repair (Includes Sidewalk/Curb & Gutter Repair)	SY	40		
24	Asphalt Pavement Repair	SY	1,000		
Total Base Bid					