



TOWN OF MOORESVILLE ENGINEERING DEPARTMENT

Record Drawing Requirements for Town of Mooresville

The Town Of Mooresville requires the following items “Record Drawings” for the above mentioned project. The record drawings shall consist of two (2) sets of mylars, one (1) set of paper, electronic files in AutoCAD and PDF format, and shall include depiction of all field changes made during construction. The drawings should include, *at a minimum*, the following: manhole rim elevations, invert elevations, storm drain pipe sizes, pipe material type, grate and invert elevations, fire hydrant locations, valve locations, fire hydrant-valve-tee distances, water and sewer service locations based on sewer manhole stationing, K-values for streets, all curve data, and label anything that is temporary. This is provided as a guide and in some cases additional information may be required. In order that corrections can be made by the inspectors before final copies are filed, please submit two paper copies. Once corrections are noted and addressed, please forward the final “Record Drawings” to the Town Of Mooresville, Engineering Department.