

Chain of Lakes City
Centennial



Celebration
1911 - 2011

July 1, 2011

Addendum 1

ITB-11-60

The Invitation to Bid – ITB-11-60 (City of Winter Haven Fiber Optic Conduit Installation Project), is hereby changed by addition of the following clarifications:

1. Boxes shall be Quazite Polymer, 24" x 36" for the pull box, 30" x 60" for the splice box. The depth of the boxes shall be 3 ft minimum. The legend "City of Winter Haven Fiber Optic Cable" shall be stamped on all covers. Lids are not traffic rated. Ground rods will not be required for the composite boxes.
2. Bore Head Diameter: The Contractor shall use the minimum appropriate pilot bit diameter to perform the bore to accommodate the proper installation of the 2-2" HDPE conduits. Accordingly, this diameter can be larger than 4" if the Contractor chooses to do so. However, special attention is required to the maximum pilot bit diameter as specified in Section "555-4.3, Product Bore Hole Diameter" in the bid documents.
3. The HDPE conduit shall be SDR 11, orange color. Couplings can be used on conduits.
4. Tracer wires are required. Refer to General Note 3 on Sheet 13. Tracer wire shall be solid # 10 gauge copper wire insulated. The insulation shall be solid orange in color. The tracer shall run continuous between the pull boxes and be sliced inside the pull box.
5. The City will not provide a location for the disposal of the bore mud. It is the Contractor's responsibility to properly dispose of the bore mud.
6. The Contractor is not responsible for the cost of any permits. However, the Contractor is responsible for the proper maintenance of traffic (M.O.T.) in accordance with the governing right-of-way authority (refer to General Note 7 on Sheet 13).
7. The Contractor shall furnish all materials, labor, equipment, and supervision necessary for a complete job. Section 1.02 "Work by Contractor" under "Summary of Work" summarizes the Contractor's responsibility. Specifically, subsection "C" states "Work to include, but not limited to: install 2-2" HDPE conduits

by directional bore; install pull boxes; install tracer wire; remove sections of existing sidewalk and replace with same kind or better; install pull wire; sod disturbed areas; maintenance of vehicular and pedestrian traffic and other incidental work necessary to complete the project". Work also includes proper backfilling and compaction. **It is the Contractor's responsibility to factor in the cost of all of the above mentioned items in his unit rates for the pay items specified in the bid schedule. The City will not be responsible for paying any additional costs for work required to complete the job that does not have a separate pay item in the bid schedule.**

8. Both the Prime Bid and the Alternate Bid shall be priced. A revised bid schedule sheet is hereby attached to this addendum (**page PBF-5a1**). The quantities of the pull boxes have been revised to reflect the correct quantities per plans. Contractor shall use the revised bid schedule sheet in their bid submittal.

All other terms and conditions remain the same.

Sincerely,

CITY OF WINTER HAVEN

A handwritten signature in black ink, appearing to read "Bob Bishop", written in a cursive style.

Bob Bishop,
Procurement Services Division Director