

# WINTER HAVEN

## *The Chain of Lakes City*

Engineering Services Division

January 30, 2012

Addendum 1

ITB-12-04

The invitation to Bid – Replacement of Lift Station # 309, ITB-12-04, is hereby changed by addition of the following clarifications:

1. **Existing Power Service:** The existing single phase electrical service will be utilized to provide power to the new three phase pumps. The control panel, which will be provided by the City, will be capable of converting the single phase to three phase. No upgrades will be required for the existing power service.
2. **Dewatering:** Dewatering will be required as specified under Section 6.11.1 "Excavation" of the City's Technical Standard Specifications. The Contractor shall factor in any additional cost for dewatering in his bid price. The discharge from the dewatering process can be directed to a nearby storm inlet by surface runoff. A gutter buddy or any other approved erosion and sediment control measure shall be used at the storm inlet.
3. **Bypass Pump System / 2<sup>nd</sup> Bypass Pump:** The Bypass Pump System shall be a dual pump system providing an automatic back-up pump for the system. The system shall also have an automatic telephone dialing system to notify the contractor and selected City employees of any pumping failure.
4. **Work Encroachment Outside the 15 ft Easement:** The City has contacted the adjacent property owners and acquired their approval for the successful contractor to encroach, within reasonable distances, inside their respective properties for the purposes of securing a safe excavation and for staging excavated material. The extend of the encroachment shall be limited to the absolute minimum as required to satisfy OSHA excavations standards. It is the Contractors responsibility to provide a safe work area, as required, protecting workers, structures, and equipment by utilizing other additional necessary sheeting, shoring, or bracing method if the conditions warrant. The contractor shall restore all disturbed areas to its original or better conditions.
5. **Materials Furnished by the City:** The float level controls and all hubs/wall penetrations will be provided as part of the materials furnished by the City. The contractor will be responsible for installation.
6. **Start-up:** A Flygt representative, in coordination with the City and the Contractor, will conduct a start up at no cost to the Contractor.
7. **Electrical Conduits:** The electrical conduits from the control panel to the wet well shall be PVC Schedule 80.
8. **RPZ Backflow Preventer:** The Contractor will not be required to install a RPZ Backflow Preventer on the existing water service; as the City will be installing one if not already installed.

# *W*INTER HAVEN

## *The Chain of Lakes City*

9. **Permits:** An electrical permit from the City's Building Division will be required from the Contractor for the electrical work. The City will waive the permit fees.

All other terms and conditions remain the same.