GUTTER AND DOWNSPOUT NOTES:
1. GUTTER - 6" ALUMINUM "K" PROFILE IN STOCK 43"H X 6"W.
2. DOWNSPOUT - 5" ALUMINUM CORRUGATED RECTANGULAR PROFILE IN STOCK 3¼" X 4¼".
3. SEE ROOF PLAN A4.1 FOR EXACT LOCATIONS OF ALL GUTTER AND DOWNSPOUTS, THE DISTANCE BETWEEN TWO DOWNSPOUTS TO BE 240' MAXIMUM, 60' MAX. IN EXTREME LOCATIONS.

BRICK CONTROL JOINT (CJ) NOTES:
1. INSTALL ½" BRICK CONTROL JOINTS LOCATED WHERE AS SHOWN ON ELEVATIONS WITH SEALANT AND BACKER ROD TO FILL THE ENTIRE LENGTH OF JOINT.
2. INSTALL ADDITIONAL MASONRY TIES ALONG BOTH SIDES OF THE CONTROL JOINT TO SECURE FACE BRICK TO THE BACK UP WALL STUD.

ROOFING NOTES:
1. INSTALL 40 MIL ICE / WATER SHIELD 4'-0" WIDE ON ROOF DECK AT EAVE EDGE, ROOF VALLEY, RAKE EDGE, CRICKET, AROUND SKYLIGHTS, ETC. AS ADDITIONAL MEASURE PRIOR TO INSTALL ADDITIONAL ROOF SHINGLES.
2. ALL ROOF VALLEYS ARE TO BE CLOSED SHINGLE VALLEYS, SEE ROOF SHINGLE TILE SPECS FOR DETAILS.

WINDOW LEGEND:
⊗ WINDOW TYPE
SEE SHEET A11.1 FOR WINDOW SCHEDULE.

Elevation Scale: 3/32"=1'-0" (9)
Elevation Scale: 3/32"=1'-0" (8)
Elevation Scale: 3/32"=1'-0" (7)
Elevation Scale: 3/32"=1'-0" (6)
Elevation Scale: 3/32"=1'-0" (5)

BRICK CONTROL JOINT THRU CMU BASE (TYP)
BRICK CONTROL JOINT AT INSIDE CORNER (TYP)
REV. FINISH

Key Plan
N.T.S.
North