QUAKER STEAK & LUBE

8700 PROTOTYPE

PROJECT TITLE:

DATE:
XX/XX/XX

ISSUED FOR:
PROTOTYPE

REVISIONS:

No.	Description:	Date:

PROJECT MANAGER:

DRAWN BY:
JJJ

PROJECT NO:
XXX

DRAWING TITLE:
0607S.000

DRAWING NUMBER:
FLOOR PLAN

A101

HC KLOVER ARCHITECT MAKES NO REPRESENTATION regarding the accuracy or completeness of these Drawings - in either printed or electronic media format, and no warranty, either express or implied, of merchantability or fitness for any particular purpose is offered. HC KLOVER ARCHITECT is not responsible or liable for any costs or damages, including but not limited to claims for loss of profit, resulting from use of these Drawings.

FLOOR PLAN

1/4" = 1'-0"

NORTH

LEGEND

- FULL HEIGHT MTL. STUD WALL (OTHERWISE NOTED)
- FULL HEIGHT MTL. STUD WALL WITH SOUND INSULATION
- CMU
- WALL BLOCKING. REFER TO KITCHEN DWGS. SHEET FS-6.0 FOR EXACT LOCATIONS, SIZES, AND HEIGHTS (KITCHEN)
- FRP OVER CMU TO 4" ABOVE CLG. SEAL ALUM. BASE OVER FRP (KITCHEN)
- STAINLESS STEEL PANEL (KITCHEN)
- ADD 1/2" PLYWOOD UNDER FINISH MATERIAL, EXCEPT AT WOOD PANELING (FRONT OF HOUSE)
- STEEL COLUMN
- BOLLARD
- WINDOWS RE: A601
- DOORS RE: A601
- WALL TYPE RE: A901

GENERAL NOTES

1. INTERIOR DIMENSIONS TO THE EDGES OF MTL. STUDS.
2. EXTERIOR DIMENSIONS ARE TO EDGE OF CMU WALLS.
3. ALL OUTSIDE CORNERS IN KITCHEN AREAS TO RECEIVE 4"H STAINLESS STEEL CORNER GUARDS.
4. DOWNSPOUTS CONNECT TO STORM SEWER (TYP.). RE: CIVIL.
5. G.C. TO PROVIDE SUN SHADES BY CASTEC OR EQUAL. USE ROLLSTAR 200 SERIES WITH VINYL-COATED POLYESTER FABRIC SCREEN. PROVIDE SAMPLES FOR APPROVAL PRIOR TO ORDERING. COORDINATE LOCATION OF SUN SCREENS WITH OWNERS REPRESENTATIVE.

HALF HEIGHT WALLS TO BE INSTALLED AFTER INSTALLATION OF CORNER BOOTH. CORNER BOOTH INSTALLER.

HANDLE BAR 111

HALF HEIGHT WALL

DOWNSPOUT DOWN TO BOOT BELOW SLOPE AWAY RE: 15AS101 TYP.

ALIGN FINISHED FACE OF STUD WALL WITH CMU

WALL BLOCKING (TYP.)

EXTENT OF STAINLESS STEEL PANELS BEHIND EQUIP. RE: FS SHEETS

CONTINUE STAINLESS PANELS PAST HOODS & WRAP END OF WALL

VEST. ROOM 112

KITCHEN 115

ALL BLOCKING OR PLYWOOD USED ADJACENT TO THE FIRE-RETARDANT TREATED.

NO FRP THIS SIDE OF WALLS

WALK IN COOLER 123

FREEZER 124

WINE COOLER 125

NOTE: RE: A106 FOR FREEZER/COOLER PLANS

SEAL AT COOLER

FRP ADHERED TO CMU. TYP.

DOWNSPOUT DOWN TO BOOT BELOW SLOPE AWAY RE: 15AS101 TYP.

GAS METER

BOLLARD (TYP.)

SIM.

GAMES 105

FETAM 104

THUNDER ALLEY 110

CORRIDOR 106

MEN'S RESTROOM 108

RESTROOM VESTIBULE 107

WOMENS RESTROOM 109

WAITING 101

HOST 103

IN FLOOR T.V. MONITOR

CMU TO STUD

VESTIBULE 100

BRICK YARD 113

LIQUOR 118

OFFICE 117

EMPLOYEE RESTROOM 119

SERVICE 120

DRY STORAGE 116

MECHANICAL 121

TRASH ENCLOSURE 122

BOLLARD RE: 3AS101

DOWN SPOUT DRAIN TO DAYLIGHT

STEEL TUBE COL. (TYP.)

NOTE: RE: A106 FOR BEER COOLER

TRANSFORMER PAD

DOWN SPOUT DRAIN TO DAYLIGHT

DOWNSPOUT DOWN TO BOOT BELOW SLOPE AWAY RE: 15AS101 TYP.

6"X6" CEDAR POST BELOW TOP RAIL